




Coal Pensions – ARM Headquarters

Kier Construction Eastern, Exemplar BIM Project



Presentation Agenda



- Introduction to ARM and Project Overview
- Client BIM Objectives and Aspirations
- Project BIM Scope
- Project BIM Set Up
- Case Studies, Examples and Lessons Learnt
- Conclusion

ARM




“ A Press release ”

In a loose collection of offices on an underwhelming business park outside of Cambridge sits Britain’s most successful technology company, ARM. You’ve probably never heard of it, but ARM’s designs are at the heart of the iPhone and nearly every other modern smartphone. It has fingers in almost every other area of technology, from fitness trackers to server farms. It records profit margins that analysts have described as “impossible” (in a good way), and goes a long way to helping justify the “Silicon Fen” label sometimes applied to Cambridge’s tech scene.


Project Overview



The ARM Peterhouse Technology Park Expansion Project involves the construction of a new 19,000 m² office facility and two multi storey car parks including associated earth works and infrastructure works.



Overview of Construction Scope



Design – Key Capabilities & Designers



Our client team is :-

Coal Pensions Properties Limited
LaSalle Investment Management
Bidwells
Aecom

Consultants

- Architect – Scott Brownrigg
- Civil & Structure – Ramboll
- M&E - Hoare Lea
- Landscape – Liz Lake

Subcontractors with Design Input

- Façade – McMullen
- Steel Frame – Caunton
- M&E – Integral
- Upper Floors – SMD
- Decked Car Parks – Bourne/ Huber
- Feature Stairs – Taunton
- Flat and Brown Roofs - Avonside



How was BIM utilised?

Client BIM Objectives and Goals



Pre Contract BIM Execution Plan

Primary Objectives	Description / Potential BIM Uses
3D Coordination	Design team to link respective models throughout the design and potentially the construction process.
Visualisation	Aid Design Team in showing the proposals in three dimensions.
Site Analysis	Using the Revit model to show the challenges of existing levels and the proposed building platforms.

NBS Clause

Finishes

Early Quantity Checks


Consultant's Design Models

- An initial test project was created within BIMXtra for internal use only to generate schedules and review the design in the 3D environment for **validation of initial quantities**.
- **Highlighting Potential discrepancies** in the quantities calculated through traditional techniques for the intricate façade structure.
- The Bid Team **gained extra confidence in the quantities** outlined within the bid submission for the building envelope.



Case Study – Early Quantity Checks

KB203 – Consultant's Design Model



Federated model in Navisworks

THE PROJECT

ARM expansion, Peterhouse Technology Park

THE CLIENT

Coal Pension Properties

BUILD VALUE


£30m

PROJECT TEAM

KCE
Scott Brownrigg (Architecture)
Ramboll (Structures)
Hoare Lea (MEP)

PROJECT OVERVIEW

The proposal is to demolish ARM 2 and construct 2 new buildings (ARM A and B) by extending the park into the adjacent Green Belt. The buildings will be of unequal size and approximately 17,000m² NIA. The works also include new car parks at grade and multi-deck.



Federated Model with the BIMXtra Highlighter selecting components

Early access to the novated design consultant's BIM models allowed the Bid Team to visualise the design in 3D and validate traditional initial quantity take offs.

What we did: An initial test project was created within BIMXtra for internal use only. The BIMXtra Information Exchange workflow was conducted by the BIM Coordinator to generate basic schedules and allow the Bid Team to review the design in the 3D federated model environment and validate initial quantities.

Why/How we did it: This process enabled us to highlight any potential discrepancies in the quantities calculated through traditional techniques. This was particularly important with the intricate façade structure, where areas of the building envelope overlapped one another and were hidden on elevation drawings. By navigating around the federated model in 3D the Bid Team were able to visualise the design and cross reference mapped components within the BIM Schedules against those included within the Bill of Quantities.

The Benefits were: The Bid Team gained extra confidence in the quantities outlined within the Bid Submission for the building envelope.

'The early mapping of the model not only allowed the quantities to be checked but also allowed the potential for value engineering through changes in specification to be demonstrated and evaluated with the design team.'

Rob Brady – Senior Bid Manager – KCE

© Kier 2015

BIM Coordinator – Rebecca Glennon (KCE)

BIM Case Study – No. 0023 – July 2015

Kier BIM Menu Version 1



Common Data Environment Solution




BIMXtra



- **BIMXtra identified as the CDE** for the project to facilitate Level 2 BIM maturity
- The BIMXtra Document Management module has been used to **manage shared and published model information.**
- Viewpoint for Projects has been used in conjunction with BIMXtra to **manage all other published information.**

Project BIM Scope



Internet Connection Is Key

Poor Internet Connectivity



- Works on site commenced July 2016.
- Adequate internet connection was not available until January 2017.
- Extremely Poor download speeds



Lessons Learnt

Common issue across the Construction Industry. Further investigation and innovation required to speed up on site connection provisions.




Specialist Modelling Tools

Tekla Structures Workflow

- Improved understanding of complex junctions not available within the Structural Engineer's model.
- Assisting with visual audits of design and enabling clash avoidance workflows to further rationalise and coordinate the design.
- Reduction in time to translate information.
- Accuracy of locational coordinates improved.

Lessons Learnt

Early Subcontractor engagement required to incorporate into project BEP and undertake new workflow training and testing.



A brief overview of the project

ARM requires the consolidation of their staff in Cambridge onto Peterhouse Technology Park. They occupy four existing buildings on the site. Kier have been contracted to demolish one existing building and construct two new buildings (ARM A and B). The buildings will be of unequal size and approximately 17,000m² NIA.

The challenge

The BIM process requires all models to be shared and coordinated on a project. The task of coordinating these can become complex when models are developed in various software packages. Historically, it has been a challenge to incorporate steel fabricators models into this process but this is an essential requirement for design reviews to take place in a 3D environment. Specialist consultants produce models in a way that aids the fabrication process, but this does not provide the real world coordinates that are required to produce a federated models.



The actions

- To reduce the amount of work required to make manual adjustments to coordinates an early engagement workshop was held with the specialist consultants (Cauntons Engineering Ltd) to discuss alternative export arrangements.
- A new export routine was developed using Plug Ins within Tekla
- It was requested that any new models provided to Kier followed this new process to ensure coordinates were accurate.

The benefits

- Improved understanding of complex junctions not available within the Structural Engineer's model
- Assisting with visual audits of the design and enabling clash avoidance workflows to further rationalise and coordinate the design.
- Reduction in time to translate information
- Accuracy of locational coordinates improved

Client

Coal Pension Properties

Location

Cambridge

Project type

Commercial

Value

£49m

Start date

July 2016




GR001-KCE-MK-204-CS-BM-0001_Specialist Models

Kier Construction Eastern


Model Viewing Tools



BIMxtra Highlighter



- Highlight items by BIMxtra schedules or work packages in 3D only.
- Clash Detection/ Avoidance Workshops
- Design Coordination
- Quality Assurance



- Highlighting items by BIMxtra schedules or work packages in 3D and intelligent 2D Drawings.
- Field BIM Site Form Completion.
- Model & Site Audit
- Offline Mode



Hardware Procurement



Clevertouch Plus Screen


- Viewing Drawings and annotating solutions
- Viewing models and annotating ideas
- Detailed Programme
- Method Statements
- Presenting progress reports in Client Meetings
- Convenience of writing minutes with attachments within the meetings.
- It is a very usable piece of equipment which is used by all on site daily.



Design Coordination

Communication of Requirements

- To illustrate scale of project – federated models Scott Brownrigg, Caunton, Integral, & Huber



Design Coordination



Communication of Requirements

- To illustrate façade fixing requirements to specialist fixings supplier


Message to specialist fixings supplier:

“The floor slab construction is as follows:

130mm thick RC floor on an R51 Structural Metal Deck

At 2nd floor level we need a slab edge fix solution.

At 1st floor we can do either a slab edge or top fix solution.”



Design Coordination

Coordination of Services



BIMXtra



Clash Report

Peterhouse

Clash Tests in this document:

- Steel vs Ducts (34 clashes)

Document Number: ARM-SBR-B1-CR-001
Revision: A
Document Generated: 19/05/2016


Clash detection report generated by Scott Brownrigg architects between Caunton Steel model and Integral M&E model

Document Number: ARM-SBR-B1-CR-001

Page 1 of 19


Peterhouse

BIMXtra



Name	Clash1
Distance	-101.446mm
Status	New
Description	Hard
Point	548017262.54mm, 255955240.07mm, 29902.01mm

Item1	
Layer	Undefined
Item Type	LcIFCRepresentationHolder
Item Name	Body
Item2	
Handle	3140426
Layer	D1-Level 1
Item Type	Solid
Item Name	Rectangular Duct



Name	Clash2
Distance	-94.114mm
Status	New
Description	Hard
Point	548071539.23mm, 255950570.85mm, 33726.60mm

Item1	
Layer	Undefined
Item Type	LcOaBGeometry
Item Name	#291144
Item2	
Handle	6743561
Layer	D2-Level 2
Item Type	Solid
Item Name	Toilet Extract

Document Number: ARM-SBR-B1-CR-001



Page 2 of 19

Design Coordination



Coordination of Services



- Model snapshot used in DTM to illustrate where a clash with steelwork and services had been picked up using clash detection to identify further service penetrations required
- Model snapshot used to confirm to ARM Fit Out Team that the bracing had been raised to provide full depth use of beam cut outs for the fit out services



Design Coordination

Coordination of Services

- Model snapshot exchanged with multiple comments used to develop solutions for service penetrations through the steelwork.




Design Coordination



Coordination of Services

- Model snapshot used in DTM to illustrate where there was clash with future tenant ductwork connection and base build cable trunking.
- Different elements can be colour coded and made transparent.
- Clash was not picked up by clash detection tool as no fit out ductwork in the federated model




Management of Client Change

Question to Client

“Can you advise where you got to with COR 19 re-routing of services out of “tenant zone” for the atrium FCU’s.


We have not received any information yet.

Currently our design is as screen shot below which follows the Hoare Lea Design Intent in the ERs”



Management of Client Change

COR 19 – Ground floor ceiling adjacent to atrium



Services requested to be relocated to walkway zone



Key Points

- 1 – supply outlets go to a ceiling mounted grill as shown
- 2 – fresh air supply ducts to each fan coil unit not required, alternative fresh air supply distribution proposed, need to verify this will work
- 3 – water services and condensate to be moved to ceiling void or in floor void above. Consider leak detection.
- 4 – trunking to be moved to ceiling void or floor void above
- 5 – consider making slope of ceiling shallower to allow fan coil unit to move closer to atrium and create more space for relocated services

Management of Client Change



COR 19 – Ground floor ceiling adjacent to light well




Key Points

- 1 – supply outlets need to set down and terminate in grill in bulkhead facia – there are tenant offices below, so cannot be in a ceiling grill
- 2 – fresh air supply ducts to each fan coil unit not required, alternative fresh air supply distribution proposed, need to verify this will work
- 3 – water services and condensate to be moved to ceiling void or in floor void above. Consider leak detection.
- 4 – trunking to be moved to ceiling void or floor void above

Quality Control

Quality Control of Installation

- M&E Sub-contractor Model reviewed against installation for on site audit.



- As installed images used to convey non conformance




Design Coordination



Coordination of Services

- Failure to update models where info comes from 3rd party designers who are working in 2D
- M&E design is also subcontracted out by M&E subcontractor
- Syphonic drainage pipework clearly can't go here and the issue has been resolved in the specialist subcontractor's design, but not yet updated within the M&E model –further issues may not be realised.



Lessons Learnt

This could be tracked by using the BIMXtra/ Insight RFI and Commenting tool to capture design sketches/ minor changes to ensure they are actioned and updated within the 3d model. Responsibility lies with the subcontractor/ design consultant to complete the changes.

BIMXtra Design Schedules



High Quality Data

- All design consultants agreed to populate their BIMXtra schedules to a high

Lessons Learnt

- The Kier Team requested the Design Consultants to also produce schedules using their standard workflows alongside populating the BIMXtra Schedules to validate the information, which essentially was **doubling their efforts**. Only necessary through the transition period to gain user confidence on new workflows within the BIMXtra platform.

Information Exchanges took place on a fortnightly basis or upon sufficient change.



- Design changes could be tracked** through the BIMXtra Schedule summary page.
- The data held within the **BIMXtra schedules is linked to the 3d and 2d information** through the mapping process.

Components	Status	Δ	Rev	Total	Amendments			Unchanged	Non Compliant	RFIs	PoW LoD	% Complete
					New	Changed	Deleted					
External Works												
Facilitating Works												
Finishes												
HVAC Components				142	54	20		88				
Air Handling Unit				4		16		4				
Fan				4				4				
Fan Coil and Induction Unit				78	4	4		74				
HVAC Capital Plant				6				6				
Supply and Extract Air Terminal				50	50			0				
Manual Components												

Single Source of Information



- Drawings manually downloaded from 4 Projects and uploaded onto BIMXtra to enable 3D to 2D functionality within Insight.
- Schedules grouped retrospectively into work packages by project Quantity Surveyor.




Lessons Learnt

- The whole project team need to be committed to the process. For example the work package process needs to be led by the commercial team in line with the procurement programme to ensure information is accessible by the Project Team.

BIMXtra Insight Field BIM



Workflow Tests




BIMXtra Insight Field BIM



Workflow Tests

- Currently in progress: 7 snags/ Non Conformances highlighted to be raised digitally via Insight alongside traditional methods.
- Surface Pro 4's and field BIM application enables immediate accurate recording and reporting to subcontractors of defects, saving site team time.



Lessons Learnt

Engaging with the supply chain is key to ensure they are capable and involved in using digital construction workflows and procedures.

To conclude



Benefits

- Early Quantity Checks added confidence in measured bills.
- The ability to view all disciplines models including the steel fabricators model enabled us to view final steel connections in detail, improving design coordination with M&E and reduced clashes on site.
- Communication of construction information through marked up model view snapshots.
- Smart Screen facilitates improved problem solving through mark ups and as a presentation tool for reviewing detailed programmes, method statements and sequencing works (endless uses).
- Work packaging undertaken highlights scope of works for subcontractors and groups with 2D & 3D design information within Insight allowing project team with full access to project information on site.
- Field BIM workflow enables immediate accurate recording and reporting to subcontractors of defects, saving site team time.

To conclude



Lessons Learnt & Ideas for the future

- Early engagement with Subcontractors to ensure BIM Capability is assessed prior to appointment.
- Internet Connection is Key.
- Small design changes are neglected and are not always recorded back into the models. Design Changes to be updated in models from initial sketches to ensure full coordination impacts are realised. (This could be managed through the RFI Commenting tool via Insight/ BIMXtra)
- The whole project team need to be committed to the process. For example the work package process needs to be led by the commercial team in line with the procurement programme.



Thank you
Q&A Session